

# Gulf Stream<sup>®</sup>

Swimming Pool Heat Pumps

PERFORMANCE

EFFICIENCY



10 YEARS PARTS

2 YEARS LABOR



**HE-2 SERIES**  
SEE COMPLETE WARRANTY FOR DETAILS



[WWW.GULFSTREAMHEATPUMP.COM](http://WWW.GULFSTREAMHEATPUMP.COM)





PERFORMANCE AND EFFICIENCY:	INTELLIGENT CONTROL: (Additional wiring may be required)
<b>Ultra-Quiet Design</b> Quiet scroll compressor Commercial grade fan motor designed for quiet operation	<b>Compatible with all external Automation</b> Simple connection and programming Seamless integration with all major brands of automation
<b>4-Sided Evaporator Coil</b> Super-sized for maximum efficiency Higher Performance in all weather Engineered for a smaller footprint	<b>GPS Affordable Spa Automation</b> Isolates the spa, energizes the pump & switches thermostats Plug-ins for 2 actuators Wireless options available
<b>2" Full Flow Titanium Heat Exchanger</b> Pipe size does not reduce once inside the unit Maximum water flow design for higher efficiency Titanium not affected by pool chemistry	<b>Solarwize Solar Heating Controller</b> Solar pool automation for hybrid pool heating control Prioritizes solar pool heating for maximum efficiency Actuator Plug-in & roof sensor connections
<b>Ultimate Warranty</b> Industry Best: 2-Years Labor / 10-Years Parts	<b>Even Heat</b> Maintains the perfect temperature 24-hours a day

## ADVANCED ASSEMBLY AND TESTING

<b>Helium Leak Testing</b> 100-times more accurate than the competition Ensures optimized performance in every unit	<b>Mass Flow Charging</b> The most accurate way to ensure proper refrigerant charging Computerized accuracy to 1/100th of an ounce
<b>Rust Proof ABS Cabinet</b> Strong ABS cabinet designed for harsh climates UV inhibitors added for lifetime durability Avoid the metal-cabinet regret	<b>Comprehensive Final Run Test</b> Computerized quality control testing cannot be bypassed Every-component in every-unit tested every-time A "Perfect" unit every time for the ultimate peace of mind

UNIT SPEC	HI-110	HI-125	HI-150
BTU/COP <b>AHRI HIGH TEST POINT(80/80/80)</b> LOW TEST POINT (50/63/80)	<b>110,000/6.2</b> 66,000/4.1	<b>122,000/6.1</b> 74,000/4.0	<b>136,000/6.0</b> 85,000/4.0
<b>MIN AMPS / MAX BREAKER</b>	<b>37/40</b>	<b>37/50</b>	<b>37/50</b>
<b>WEIGHT (SHIPPING)</b>	215 LBS (243 LBS)	237 LBS (265 LBS)	239 LBS (267 LBS)
<b>DIMENSIONS (SHIPPING)</b>	31 X 31 X 38 (33 X 31 X 43)	31 X 31 X 42 (33 X 31 X 47)	31 X 31 X 42 (33 X 31 X 47)



[WWW.GULFSTREAMHEATPUMP.COM](http://WWW.GULFSTREAMHEATPUMP.COM)

